

HTE# 07-5-1773

Harnock County Department of Public Health

24084

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: MARKS RD

ISSUED TO: SPOUT SPRINGS CHURCH OF CHRIST

SUBDIVISION _____

LOT # _____

NEW REPAIR EXPANSION

Site Improvements required prior to Construction Authorization Issuance: _____

Type of Structure: CHURCH

Proposed Wastewater System Type: CONVENTIONAL

Projected Daily Flow: 162 GPD (54 MEMBERS)

Number of bedrooms: _____ Number of Occupants: 54 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 100 feet

Permit valid for: Five years No expiration

Permit conditions: _____

Authorized State Agent: _____

Date: 7/30/07

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: SPOUT SPRINGS CHURCH OF CHRIST

PROPERTY LOCATION: MARKS RD

SUBDIVISION _____

LOT # _____

Facility Type: CHURCH New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** CONVENTIONAL (Initial) Wastewater Flow: 162 GPD

(See note below, if applicable)

CONVENTIONAL (Repair)

Installation Requirements/Conditions

2 TRENCHES

Septic Tank Size 1000 gallons

Exact length of each trench 50 feet

Trench Spacing: 9 Feet on Center

Pump Tank Size _____ gallons

Trenches shall be installed on contour at a

Soil Cover: 24 inches

Maximum Trench Depth of: 36 inches

(Maximum soil cover shall not exceed

(Trench bottoms shall be level to +/-1/4"

36" above the trench bottom)

in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

Conditions: TANK LOCATION REQUESTED BY APPLICANT BASE ON FLAGS ON SITE

12 inches total

**If applicable: *I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: _____

Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: _____

Date: 7/30/07

Construction Authorization Expiration Date: 7/30/12

