HTE# 15-5-36334R ~~GARAGE~~
15-5-35723R ~~HOUSE~~

Harnett County Department of Public Health

28735

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: Tirzah Dr.

ISSUED TO: John Schuman

SUBDIVISION Tirzah Village   LOT # 4

NEW ☒   REPAIR ☐   EXPANSION ☐   Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFO (72 × 62)

Proposed Wastewater System Type: 25% Reduction System

Projected Daily Flow: 360 GPD

Number of bedrooms: 3   Number of Occupants: 6   max

Basement ☐Yes ☒No

Pump Required: ☐Yes ☒No   ☐ May be required based on final location and elevations of facilities

Type of Water Supply: ☐ Community ☒ Public ☐ Well   Distance from well 100 feet   Permit valid for: ☒ Five years

Permit conditions: _____   ☐ No expiration

Authorized State Agent:: _____   Date: 5/17/16   SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit..

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958. and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: John Schuman

PROPERTY LOCATION: Tirzah Dr

SUBDIVISION Tirzah Village   LOT # 4

Facility Type: SFO (72 × 62)   ☒ New ☐ Expansion ☐ Repair

Basement? ☐ Yes ☒ No   Basement Fixtures? ☐ Yes ☒ No

Type of Wastewater System** 25% Reduction System   (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable ☐) 25% Reduction Sys (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons   Number of trenches 3

Pump Tank Size _____ gallons   Exact length of each trench 50 feet   Trench Spacing: 9 Feet on Center

Trenches shall be installed on contour at a   Soil Cover: 6-18 inches

Maximum Trench Depth of: 18-30 inches   (Maximum soil cover shall not exceed

(Trench bottoms shall be level to +/-1/4"   36" above the trench bottom)

in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM

_____ inches below pipe

Aggregate Depth: _____ inches above pipe

Conditions: _____   _____ inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

If applicable: *I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: _____   Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.   SEE ATTACHED SITE SKETCH

Authorized State Agent: _____ RGHS   Date: 5/17/16

Construction Authorization Expiration Date: 5/17/21

HTE# 15.5-35723R   Permit # 28735

Harnett County Department of Public Health
Site Sketch

ISSUED TO: _John Schuman_

PROPERTY LOCATON: _Tizzah Dr_

SUBDIVISION _Tizzah Village_   LOT # _4_

Authorized State Agent: _RGHS (Oliver Tolksoor)_   Date: _5/17/16_

*GARAGE
REMOVED
FROM SITE
PLAN

REPAIR
AREA

HOUSE

DRIVE

R45