

Fire Marshal/Emergency Management

Mailing: P. O. Box 370 Lillington, NC 27546
Physical: 200 North 13th Street, Suite 19
Erwin, NC 28339

910-893-7580
910-893-5025

APPLICATION FOR PLAN REVIEW

APPLICATION NUMBER: 09-50022911
TODAY'S DATE: 11.12.09 RECEIVED BY: djohnson
SUBMITTED BY: Camera Premier Properties
NAME OF PROJECT: David E. Galatas, DDS.
PHYSICAL ADDRESS: NC Hwy 24/87
PHONE NUMBER: _____ EXT.: _____
CONTACT PERSON: _____
MAILING ADDRESS: _____
PHONE NUMBER: _____
CONTRACTOR'S NAME: _____
MAILING ADDRESS: _____
PHONE NUMBER: _____

NOTICE

PLANS THAT ARE SUBMITTED WILL BE REVIEWED AS QUICKLY AS POSSIBLE, WITH AN AVERAGE TIME OF REVIEW BETWEEN 7 - 10 WORKING DAYS.

Submitted plans to FM 11.12.09



Plan Review, Inspection and Permit Fees

Application Number 09-50022911

\$150.00	<input type="checkbox"/>	Explosive Mat. (90 Days)
\$ 75.00	<input type="checkbox"/>	Explosive Mat. (72 Hrs)
\$ 25.00	<input type="checkbox"/>	Fireworks Public Display
\$ 35.00	<input checked="" type="checkbox"/>	Final Inspection
\$ 35.00 +2.00 per device	<input type="checkbox"/>	Fire Alarm Testing
\$ 35.00 + 2.00 per nozzle	<input type="checkbox"/>	Fixed Fire Suppression
\$ 25.00	<input type="checkbox"/>	Insecticide Fog/Fumigation
\$ 50.00	<input type="checkbox"/>	Pipe Test/UST/AGST
\$ 50.00	<input checked="" type="checkbox"/>	Plans up to 5000 ft ²
\$100.00	<input type="checkbox"/>	Plans 5001 ft ² to 10,000 ft ²
\$150.00	<input type="checkbox"/>	Plans 10,001 ft ² to 25,000 ft ²
\$250.00	<input type="checkbox"/>	Plans 25,001 ft ² and over
\$ 35.00 + 2.00 per Head	<input type="checkbox"/>	Sprinkler Certification Test
\$ 35.00	<input type="checkbox"/>	Standpipe Testing
\$ 25.00	<input type="checkbox"/>	Special Assembly
\$ 25.00	<input type="checkbox"/>	Temporary Kiosks/Displays
\$ 25.00	<input type="checkbox"/>	Tents, Canopies, Air Supported
\$ 50.00	<input type="checkbox"/>	Tank Installation (charge for each tank)
\$ 50.00	<input type="checkbox"/>	Tank Removal (charge for each tank)

\$ 85.00 Total

Total device/heads

Teddy Joe McLamb
Code Enforcement Official

11/24/09
Date



Fire Marshal Division

November 24, 2009

David Galatas
NC 24/87
Cameron, NC 28326

David Galatas, DDS
NC 24/87
Cameron, NC 28326

Application Number 09-50022911

Mr. Galatas,

Thank you for submitting the plans for the DDS building. The plans have been carefully reviewed by a qualified code enforcement official to examine for full compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **906.1 Fire Extinguishers**
 - Fire extinguishers shall be placed in approved locations as drawn by the code enforcement official on the approved plans.
 - The fire extinguishers provided shall have a minimum rating of 2A 10B:C and shall not be installed higher than 5 feet above the finished floor

- **506.1 Knox Box**
 - A secure key box shall be installed on the new building that houses all keys to all the doors within the building in which the fire department would need access to in the event of an emergency.
 - Knox Box ID stickers shall be placed on all exterior doors in which entry to the building may be gained.
 - The box shall be mounted not to exceed 48 – 60 inches in height.
 - An authorized order form is included with this letter.



- **505.1 Physical Address**
 - The physical address of the building shall be posted in a conspicuous place so that it can be seen on approach from the road, access road, and/or parking lot.
 - The numbers used to make up the physical address shall be at least 5 inches in height

- **503.1.1 Fire Department Access**
 - The fire department access shall extend to within 150 feet of all portions of the facility.
 - The fire department access road shall be of an unobstructed width of not less than 20 feet and shall have an unobstructed vertical clearance of not less than 13 feet 6 inches.

- **508.5.1 Fire Hydrants**
 - In accordance with the Fire Code, a hydrant must be within 400' of a new occupancy classification in which your building would be categorized in.

- **1006.1 Illumination required.**
 - The means of egress, **including the exit discharge**, shall be illuminated at all times the building space served by the means of egress is occupied.
 - Emergency lights shall be installed to illuminate the path of egress travel

Thank you again for submitting the plans for the DDS building. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office.

Again, thank you and we look forward to working with you during the construction period!

Sincerely,

Teddy Joe McLamb

T.J. McLamb, CFI
Chief Deputy Fire Marshal