

# OPERATIONS PERMIT

Name: (owner) Pine Grove Dev.  New Installation  Septic Tank  
 Property Location: SR# 1114  Repairs  Nitrification Line  
 Subdivision Farm @ 5 Ponds Lot # 38  
 TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: Ted Brown Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:   
 Water Supply:  Well  Public  Community  
 Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other \_\_\_\_\_

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 400 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain: \_\_\_\_\_ Linear feet

Date: 12-1-00

PERMIT NO. 16755

Inspected by: Joe Waters  
Environmental Health Specialist

