

00-50000792

HAMILTON COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH SECTION

No 14307

OPERATIONS PERMIT

Name: (owner) Pine Grove Dev. New Installation Septic Tank
 Property Location: SR# 1114 Repairs Nitrification Line
 Subdivision Farm @ Five Ponds Lot # 50
 TAX ID# _____ Quadrant # _____
 Contractor: Ted Brown Registration # _____

Basement with Plumbing: Garage:
 Water Supply: Well Public Community
 Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____
 Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons
 Subsurface Drainage Field: No. of ditches 1 exact length of each ditch 240 ft. width of ditches 3 ft. depth of ditches 18 in.
 French Drain: _____ Linear feet

PERMIT NO. 17001 Date: ~~01-19-01~~ 01-19-01
 Inspected by: J. L. Wray
 Environmental Health Specialist

