

HTE 01-5-2825

# OPERATIONS PERMIT

Name: (owner) SARAH GREGORY  New Installation  Septic Tank  
 Property Location: SR# NC27 (TACIA DR)  Repairs  Nitrification Line  
 Subdivision COOPERS PLACE Lot # 4  
 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: HAL BROWN Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 100 ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other PUMP TO POLYSTYRENE AGGREGATE TRENCH

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface	No. of	exact length	width of	depth of
Drainage Field	ditches <u>2</u>	of each ditch <u>150</u> ft.	ditches <u>3</u> ft.	ditches <u>18</u> in.

French Drain Required: \_\_\_\_\_ Linear feet

Date: 2/14/05  
 Inspected by: [Signature] Environmental Health Specialist

PERMIT NO. 19809

