

OPERATIONS PERMIT

01-5-3389

Name: (owner) Pine Grove Dev. New Installation Septic Tank
 Property Location: SR# 1114 Repairs Nitrification Line
 Subdivision Farm 0.5 Ponds Lot # 48
 TAX ID# _____ Quadrant # _____
 Contractor: T. Brown Registration # _____

Basement with Plumbing: Garage: *NOTE Repair is pretreatment*
 Water Supply: Well Public Community *To LPP*
 Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other Pump to Conv.
 Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons
 Subsurface Drainage Field: No. of ditches 4 exact length of each ditch 75 ft. width of ditches 3 ft. depth of ditches 18 in.
 French Drain: _____ Linear feet

Date: 12-18-01

PERMIT NO. 18931

Inspected by: Joe Waters
Environmental Health Specialist

