

# OPERATIONS PERMIT 2-5-4446

Name: (owner) Robert Cieri  New Installation  Septic Tank  
 Property Location: SR# NC 84127  Repairs  Nitrification Line  
 Subdivision The Highland C Shermans Forest Lot # 10  
 TAX ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: L. Sharpe Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50 ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other \_\_\_\_\_

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 240 ft. width of ditches 3 ft. depth of ditches 18-24 in.

French Drain: \_\_\_\_\_ Linear feet

Date: 5-3-02

PERMIT NO. 19050

Inspected by: Joe WARS  
Environmental Health Specialist

