

OPERATIONS PERMIT

03-5-5074

Name: (owner) Pine Grove New Installation Septic Tank
Property Location: SR# 1141 Repairs Nitrification Line
Subdivision Heather Brooke Lot # 63
TAX ID# _____ Quadrant # _____
Contractor: T. Brown Registration # _____

Basement with Plumbing: Garage:
Water Supply: Well Public Community
Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____
Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons
Subsurface Drainage Field: No. of ditches 1 exact length of each ditch 300 ft. width of ditches 3 ft. depth of ditches 18 in.
French Drain: _____ Linear feet

PERMIT NO. 19491 Date: 11-19-02
Inspected by: Jon Waters
Environmental Health Specialist

