

OPERATIONS PERMIT

03-5-5737

Name: (owner) Pine Grove Dev. New Installation Septic Tank
Property Location: SR# NC 24/27 Repairs Nitrification Line
Subdivision WOODBRIDGE Lot # 32
TAX ID# _____ Quadrant # _____
Contractor: Ted Brown Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 240 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain: _____ Linear feet

Date: 01-07-03

PERMIT NO. 19781

Inspected by: Joe WARS
Environmental Health Specialist

