

HTE# 09-5-21757

Hamilton County Department of Public Health

25311

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: CHOO CHOO HOMES
 NEW REPAIR EXPANSION
 Type of Structure: Man. Home (28x76)
 Proposed Wastewater System Type: FILL SYSTEM
 Projected Daily Flow: 480 GPD
 Number of bedrooms: 4 Number of Occupants: 8 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100 feet
 Permit conditions:

PROPERTY LOCATION: BUNNLEVEL-ERWIN RD (THINK SMART LN)
 SUBDIVISION PAMELA WILLIAMS LOT # 3

Site Improvements required prior to Construction Authorization Issuance:

Permit valid for: Five years
 No expiration

Authorized State Agent: [Signature] RS Date: 4/14/09 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: CHOO CHOO HOMES PROPERTY LOCATION: BUNNLEVEL ERWIN RD (THINK SMART LN)
 SUBDIVISION PAMELA WILLIAMS LOT # 3

Facility Type: Man Home (28x76) New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** FILL SYSTEM (PRESSURE MANIFOLD) (Initial) Wastewater Flow: 480 GPD
 (See note below, if applicable
FILL SYSTEM (Repair)

Installation Requirements/Conditions
 Septic Tank Size 1000 gallons
 Pump Tank Size 1000 gallons
 Number of trenches 10
 Exact length of each trench 160 feet
 Trench Spacing: * Feet on Center
 Trenches shall be installed on contour at a
 Maximum Trench Depth of: * inches
 (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom)
 in all directions) *SEE DESIGN SHEETS

Pump Requirements: _____ ft. TDH vs. _____ GPM
MANIFOLD - 6" MANIFOLD; 10 1/2" SCH 40 VALVES; 2' PRESSURE HEAD Aggregate Depth: 6 inches below pipe
SEE ATTACHED INFORMATION FOR MINIMUM FILL SPECIFICATIONS. 12 inches above pipe
12 inches total

Conditions: SEE ATTACHED INFORMATION FOR MINIMUM FILL SPECIFICATIONS.
AREA FOR FILL SYSTEM NEEDS TO BE VERIFIED AND FINAL FILL AMOUNT DETERMINED AFTER AREA IS CLEARED. BASED ON TOPOGRAPHY THE FILL AMOUNT REQUIRED MAY INCREASE.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
 Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] RS Date: 4/14/09
 Construction Authorization Expiration Date: 4/14/14

HTE# 09-5-21757

Permit # 25311

Harnett County Department of Public Health Site Sketch

ISSUED TO: CHOO CHOO HOMES PROPERTY LOCATOR: BUNNLEVEL ERWIN RD
SUBDIVISION: PAMELA WILLIAMS LOT # 3

Authorized State Agent: ~~OLIVER TOLKSDORF~~ Date: 4/14/09

