

HTE# 10-5-24872

Harnett County Department of Public Health

26182

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Randy Kruse Thomas PROPERTY LOCATION: Lee County Line Rd.
 NEW REPAIR EXPANSION SUBDIVISION _____ LOT # _____
 Type of Structure: DW MH 28x60 Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: conventional
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well _____ feet Permit valid for: Five years
 Permit conditions: _____ No expiration

Authorized State Agent: Bryan McJin REHS Date: 8/5/2010 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Randy Kruse Thomas PROPERTY LOCATION: Lee County Line Rd.
 SUBDIVISION _____ LOT # _____
 Facility Type: MH New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** conventional (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable
conventional (Repair)

Installation Requirements/Conditions
 Septic Tank Size 1000 gallons Number of trenches 3
 Pump Tank Size _____ gallons Exact length of each trench 100 feet Trench Spacing: 9 Feet on Center
 Trenches shall be installed on contour at a Soil Cover: 6-12 inches
 Maximum Trench Depth of: 20-12 inches (Maximum soil cover shall not exceed
 (Trench bottoms shall be level to +1-1/4" 36" above the trench bottom)
 in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total

Conditions: Start ditches at 20 inches + run to 12 inches
Stepdown will be needed. No utilities allowed in initial or repair areas.
All water lines must be at least 10 ft from any part of septic system

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Bryan McJin REHS Date: 8/5/2010
 Construction Authorization Expiration Date: 8/5/2015

HTE# 10-5-24872

Permit # 26182

Harnett County Department of Public Health Site Sketch

ISSUED TO: Randy Kruse Thomas PROPERTY LOCATON: Lee County Line Rd.
SUBDIVISION _____ LOT # _____

Authorized State Agent: [Signature] Date: 8/5/2010

