

OPERATIONS PERMIT

Name: (owner) Scott T Denton New Installation Septic Tank
 Property Location: SR# 1703 Red Hill Church Repairs Nitrification Line
 Subdivision ST Denton Lot # 4
 TAX ID# _____ Quadrant # _____
 Contractor: Ed Hudson Registration # _____

Basement with Plumbing: Garage:
 Water Supply: Well Public Community
 Distance From Well: 50' ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____
 Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons
 Subsurface Drainage Field No. of ditches 2 exact length of each ditch 120 ft. width of ditches 3 ft. depth of ditches 18-22 in.
 French Drain: - Linear feet

Date: 2-1-02

PERMIT NO. 18641

Inspected by: James E. Manhart
Environmental Health Specialist

