

# OPERATIONS PERMIT 03-5-7698R

Name: (owner) Kevin + Dinal Gardner  New Installation  Septic Tank  
Property Location: SR# 1264 Brown Rd.  Repairs  Nitrification Line  
Subdivision Piedmont Lot # 3  
TAX ID# — Quadrant # —  
Contractor: Terry Maple Registration # —

Basement with Plumbing:  Garage:   
Water Supply:  Well  Public  Community  
Distance From Well: 50 ft. <sup>+</sup>

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other 25% Reduction/Chamber  
Size of tank: Septic Tank: 1200 gallons Pump Tank: — gallons  
Subsurface Drainage Field No. of ditches 4 exact length of each ditch 60 ft. width of ditches 3 ft. depth of ditches 22-24 in.  
French Drain: — Linear feet

Date: 11/05/03  
Inspected by: Yul H. Byrd AS  
Environmental Health Specialist

PERMIT NO. 20275

BTS 1200

3TB 106

