

HTE 03-5-7854

OPERATIONS PERMIT

Name: (owner) MOORE HOMES New Installation Septic Tank
 Property Location: SR# 1260 BAYLES RD Repairs Nitrification Line
 Subdivision RAVEN ROCK RUN Lot # 4
 Tax ID # _____ Quadrant # _____
 Contractor: RAY MOORE Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 100 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other _____

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface	No. of	exact length	width of	depth of
Drainage Field	ditches <u>1</u>	of each ditch <u>240</u> ft.	ditches <u>3</u> ft.	ditches <u>18-24</u> in.

French Drain Required: _____ Linear feet

Date: 1/2/04
 Inspected by: [Signature] RS
 Environmental Health Specialist

PERMIT NO. 20233

