

HTE# 08-500-20637

Harnett County Department of Public Health

24897

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: James Squire PROPERTY LOCATION: Smith Rd
 NEW REPAIR EXPANSION SUBDIVISION: Smith Farms LOT # 3
 Type of Structure: Mod. 27x76 - 3BR Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: GRAVEL
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100 feet Permit valid for: Five years
 Permit conditions: Meet onsite for final layout if question or problem No expiration
ARISE SUBSIST PLUMBING SHALLOW, AT GROUND LEVEL OR HIGHER WHERE SHOWN

Authorized State Agent: Ju WARR Date: 08-05-08 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: James Squire PROPERTY LOCATION: Smith Rd
 SUBDIVISION: Smith Farms LOT # 3
 Facility Type: Mod 27x76 3BR New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** GRAVEL (Initial) Wastewater Flow: _____ GPD
 (See note below, if applicable 25% Reduction sys. (Repair))

Installation Requirements/Conditions
 Septic Tank Size 1000 gallons Number of trenches 1
 Pump Tank Size _____ gallons Exact length of each trench 240 feet Trench Spacing: 9 Feet on Center
 Trenches shall be installed on contour at a Soil Cover: 6 inches
 Maximum Trench Depth of: 18 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
 (Trench bottoms shall be level to +/-1/4" in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
 Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Ju WARR Date: 08-05-08
 Construction Authorization Expiration Date: 08-05-2013

HTE# 08-500-20637

Permit # 24897

Harnett County Department of Public Health Site Sketch

ISSUED TO: JAMES SQUIRE

PROPERTY LOCATION: Su.H Rd

SUBDIVISION: Su.H FARMS

LOT # 3

Authorized State Agent: J. C. [Signature]

Date: 08-05-08

173

249

105

25'

75'

27x76 3BR

↓ 5

5

10

10

Repair Area

115

DIRT

Su.H Rd

177

To Spring Hill Ch. Rd →

Meet on site
for Final
Layout if
Problems or
Questions arise

STUB out
Plumbing
shallow, at ground
level or higher
Where shown

INSTALL 24" of gravel line
at 18"

MAINTAIN
All set backs
DO NOT DRIVE
OR PARK ON
Any part of
SEPTIC
System

248