

HTE# 08-500-21197

Harnett County Department of Public Health

25206

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Advantage Plus Housing PROPERTY LOCATION: 1228
SUBDIVISION: Wood Haven Acres LOT # 15

NEW [X] REPAIR [ ] EXPANSION [ ]
Type of Structure: Mod. 28x60-3BR

Site Improvements required prior to Construction Authorization Issuance:

Proposed Wastewater System Type: Gravel

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement [ ] Yes [X] No

Pump Required: [ ] Yes [ ] No [X] May be required based on final location and elevations of facilities

Type of Water Supply: [ ] Community [X] Public [ ] Well Distance from well 100 feet

Permit valid for: [X] Five years [ ] No expiration

Permit conditions: Meet on site for final layout maintain all setbacks
SUB out plumbing shallow, at ground level or higher where shown

Authorized State Agent: J. Wises Date: 11-26-08 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Advantage Plus Housing PROPERTY LOCATION: 1228
SUBDIVISION: Wood Haven Acres LOT # 15

Facility Type: Mod. 28x60-3BR [X] New [ ] Expansion [ ] Repair

Basement? [ ] Yes [X] No Basement Fixtures? [ ] Yes [X] No

Type of Wastewater System\*\* Gravel (Initial) Wastewater Flow: \_\_\_\_\_ GPD

(See note below, if applicable) 25% Reduction system (Repair)

Installation Requirements/Conditions
Septic Tank Size 1000 gallons
Pump Tank Size \_\_\_\_\_ gallons
Number of trenches 1
Exact length of each trench 480 feet
Trench Spacing: 9 Feet on Center
Trenches shall be installed on contour at a
Soil Cover: 4 inches
Maximum Trench Depth of: 18 inches
(Maximum soil cover shall not exceed 36" above the trench bottom)
(Trench bottoms shall be level to +/- 1/4" in all directions)

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM
Aggregate Depth: \_\_\_\_\_ inches below pipe
\_\_\_\_\_ inches above pipe
\_\_\_\_\_ inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: J. Wises Date: 11-26-08
Construction Authorization Expiration Date: 11-26-2013

HTE# 08500-21197

Permit # 25206

# Harnett County Department of Public Health Site Sketch

ISSUED TO: Advantage Plus Housing PROPERTY LOCATOR: 1228  
SUBDIVISION: WOOD HAVEN ACRES LOT # 15

Authorized State Agent: J. Carter Date: 11-26-08

