

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Brandon Forrest Nordan
PROPERTY LOCATION: Autry Rd
SUBDIVISION:
LOT # 2
NEW [X] REPAIR [] EXPANSION []
Type of Structure: SFD
Proposed Wastewater System Type: 25% Reduction System
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement [] Yes [X] No
Pump Required: [] Yes [X] No
Type of Water Supply: [] Community [X] Public [] Well
Permit valid for: [X] Five years [] No expiration

Authorized State Agent: Bryan McSwain, RCHS Date: 4/15/2015 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Brandon Forrest Nordan PROPERTY LOCATION: Autry Rd
SUBDIVISION:
LOT # 2
Facility Type: SFD [X] New [] Expansion [] Repair
Basement? [] Yes [] No Basement Fixtures? [] Yes [] No
Type of Wastewater System: 25% Reduction System (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable [])
Installation Requirements/Conditions
Septic Tank Size 1000 gallons
Pump Tank Size gallons
Number of trenches 3
Exact length of each trench 100 feet
Trench Spacing: 9 Feet on Center
Trenches shall be installed on contour at a
Maximum Trench Depth of: 18 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
Soil Cover: 6 inches
Pump Requirements: ft. TDH vs. GPM inches below pipe
Aggregate Depth: inches above pipe
Conditions: Property lines must be located. Run drain lines on contour. Stepdown may be needed. inches total

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Bryan McSwain, RCHS Date: 4/15/2015
Construction Authorization Expiration Date: 4/15/2020

HTE# 11-5-26275RR

Permit # 28277

Harnett County Department of Public Health Site Sketch

ISSUED TO: Brandon Forrest Nordan PROPERTY LOCATOR: Autry Rd.
SUBDIVISION _____ LOT # 2

Authorized State Agent: Erin McSwain, RCHS Date: 4/15/2015

