

HTE# 13-5-32574

Harris County Department of Public Health

27709

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: SL 1418 OAKRIDGE RIVERISSUED TO: Christ Kym Parrish

SUBDIVISION \_\_\_\_\_ LOT # \_\_\_\_\_

NEW ☒ REPAIR ☐ EXPANSION ☐

Site Improvements required prior to Construction Authorization Issuance: \_\_\_\_\_

Type of Structure: MODProposed Wastewater System Type: 25% REDUCEDProjected Daily Flow: 480 GPDNumber of bedrooms: 4 Number of Occupants: 8 maxBasement ☐ Yes ☒ NoPump Required: ☐ Yes ☐ No ☒ May be required based on final location and elevations of facilitiesType of Water Supply: ☐ Community ☐ Public ☒ Well Distance from well 50 feetPermit valid for: ☒ Five yearsPermit conditions: \_\_\_\_\_ ☐ No expirationAuthorized State Agent: James E. Mankin Date: 12-17-13

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: CHRIS + Kym ParrishPROPERTY LOCATION: SL 1418 OAKRIDGE RIVER

SUBDIVISION \_\_\_\_\_ LOT # \_\_\_\_\_

Facility Type: MOD ☒ New ☐ Expansion ☐ RepairBasement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ NoType of Wastewater System\*\* 25% REDUCED System (Initial) Wastewater Flow: 480 GPD(See note below, if applicable ☐ 25% REDUCED System (Repair))Installation Requirements/ConditionsSeptic Tank Size 1200 gallons

Pump Tank Size \_\_\_\_\_ gallons

Number of trenches 4Exact length of each trench 80 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 24-1/2 inches(Trench bottoms shall be level to  $\pm 1/4$ "

in all directions)

Trench Spacing: 9 Feet on CenterSoil Cover: 6 inches

(Maximum soil cover shall not exceed 36" above the trench bottom)

Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM

Aggregate Depth: 6 inches below pipe2 inches above pipeConditions: \_\_\_\_\_ 12 inches total

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.**  
**NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Mankin Date: 12-17-13Construction Authorization Expiration Date: 12-17-18

HTE# 13-5-32574

Permit # 27709

# Harnett County Department of Public Health Site Sketch

ISSUED TO: Christ & Kym Ponnish PROPERTY LOCATION: 21418th Street RD  
SUBDIVISION \_\_\_\_\_ LOT # \_\_\_\_\_

Authorized State Agent: James S. Montfort Date: 12-17-13

