

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Leslie Belsma
PROPERTY LOCATION: NC 87
SUBDIVISION: Belsma Family Partition
LOT # 2
Type of Structure: SFD-34x30-2BR
Proposed Wastewater System Type: Gravel
Projected Daily Flow: 240 GPD
Number of bedrooms: 2 Number of Occupants: 4 max
Basement: No

Pump Required: No
Type of Water Supply: Public
Permit conditions: Meet on site for final septic layout maintain all setbacks
Stub out plumbing shallow at ground level or higher where shown do not drive or park on any part of septic system keep septic system within my blue flag
Authorized State Agent: Joe West (R) Date: 02-03-09 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Leslie Belsma
PROPERTY LOCATION: NC 87
SUBDIVISION: Belsma Family Partition
LOT # 2
Facility Type: SFD-34x30-2BR New
Basement: No
Type of Wastewater System: Gravel (Initial) Wastewater Flow: 240 GPD

25% Reduction System (Repair)
Installation Requirements/Conditions
Septic Tank Size: 1000 gallons
Pump Tank Size:
Number of trenches: 3
Exact length of each trench: 100 feet
Trench Spacing: 9 Feet on Center
Soil Cover: 6 inches
Maximum Trench Depth of: 18 max inches
(Trench bottoms shall be level to +/- 1/4" in all directions)
Pump Requirements:
Aggregate Depth: 6 inches below pipe, 2 inches above pipe, 12 inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: Date:

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: Joe West (R) Date: 02-03-09
Construction Authorization Expiration Date: 02-03-2014

