

HTE# 11-5-26631

Harnett County Department of Public Health

Improvement Permit

26447

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: JOEL Michael EASON PROPERTY LOCATION: SC1538 Mabry RD
 NEW REPAIR EXPANSION SUBDIVISION Mabry LOT # 7
 Type of Structure: MOVED SFD Site Improvements required prior to Construction Authorization Issuance:
 Proposed Wastewater System Type: 25% REDUCTION Syste
 Projected Daily Flow: 360 GPD
 Number of bedrooms: 3 Number of Occupants: 6 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well 100' feet
 Permit conditions: Permit valid for: Five years No expiration

Authorized State Agent: James E. Manhart Date: 5-18-11 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: JOEL Michael EASON PROPERTY LOCATION: SC1538 Mabry RD
 Facility Type: MOVED SFD New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** 25% REDUCTION Syste (Initial) Wastewater Flow: 360 GPD
 (See note below, if applicable) Pump to 25% REDUCTION (Repair)

Installation Requirements/Conditions

Septic Tank Size <u>1000</u> gallons	Number of trenches <u>2</u>	Exact length of each trench <u>120'</u> feet	Trench Spacing: <u>9</u> Feet on Center
Pump Tank Size _____ gallons	Trenches shall be installed on contour at a Maximum Trench Depth of: <u>22'</u> inches (Trench bottoms shall be level to +/-1/4" in all directions)	Soil Cover: <u>6</u> inches (Maximum soil cover shall not exceed 36" above the trench bottom)	
Pump Requirements: _____ ft. TDH vs. _____ GPM		Aggregate Depth: <u>6</u> inches below pipe	
Conditions: _____		<u>2</u> inches above pipe	
		<u>12</u> inches total	

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.
 Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Manhart Date: 5-18-11
 Construction Authorization Expiration Date: 5-18-16

HTE# 11-5-26631

Permit # 26447

Harnett County Department of Public Health Site Sketch

ISSUED TO: JOEL MICHAEL EASON PROPERTY LOCATOR: 521538 Mabry RD
SUBDIVISION: Mabry LOT # 7

Authorized State Agent: James E. Manland Date: 5-18-11

