



Plan Review, Inspection and Permit Fees

Application Number 08 -- 50019662

\$100.00	_____	Explosive Materials (90 Days)
\$ 35.00	_____	Explosive Materials (48 Hrs)
\$ 25.00	_____	Fireworks Public Display
\$ 20.00	<u>1</u> _____	Final Inspection
\$ 25.00	_____	Fire Alarm Testing
\$ 25.00	_____	Fixed Fire Suppression
\$ 10.00	_____	Insecticide Fog/Fumigation
\$ 50.00	_____	Testing of Pipes/UST/AGST
\$ 50.00	<u>1</u> _____	Plans up to 5000 ft ²
\$100.00	_____	Plans 5001 ft ² to 10,000 ft ²
\$150.00	_____	Plans 10,001 ft ² to 25,000 ft ²
\$250.00	_____	Plans 25,001 ft ² and over
\$ 25.00	_____	Sprinkler Certification Test
\$ 25.00	_____	Standpipe Testing
\$ 25.00	_____	Special Assembly
\$ 10.00	_____	Temporary Kiosks/Displays
\$ 10.00	_____	Tents greater than 700 ft ²
\$ 50.00	_____	Tank Installation (charge for each tank)
\$ 50.00	_____	Tank Removal (charge for each tank)

\$ 70.⁰⁰/₁₀₀ Total

Michael P. Allen
Code Enforcement Official

4/08/03
Date

Mailing: P. O. Box 370 Lillington, NC 27546
Physical: 200 North 13th Street, Suite 19
Erwin, NC 28339

910-893-7580
910-893-5025

APPLICATION FOR PLAN REVIEW

APPLICATION NUMBER: 08 - 50019662

TODAY'S DATE: 3-14-08 RECEIVED BY: ASB

SUBMITTED BY: Yogi Barwick

NAME OF PROJECT: HK6A Building

PHYSICAL ADDRESS: Lot 6 Progress Drive

PHONE NUMBER: (919) 677-1223 EXT.: _____

CONTACT PERSON: Yogi Barwick

MAILING ADDRESS: 4509 Creedmoor Rd, Ste 100 Raleigh, NC 27612

PHONE NUMBER: (919) 816-9995

CONTRACTOR'S NAME: Annis Building Corporation

MAILING ADDRESS: 4509 Creedmoor Rd, Ste 100 Raleigh, NC 27612

PHONE NUMBER: (919) 816-9995

NOTICE

PLANS THAT ARE SUBMITTED WILL BE REVIEWED AS QUICKLY AS POSSIBLE, WITH AN AVERAGE TIME OF REVIEW BETWEEN 7-10 WORKING DAYS.



April 8, 2008

Yogi Barwick
4509 Creedmor Road Suite 100
Raleigh, NC 27612

HK&A Building
Progress Drive
Fuquay Varina, NC 27526

Application Number 08-50019662

Mr. Barwick,

Thank you for submitting the plans for the office building. The plans have been carefully reviewed by a qualified code enforcement official to examine for full compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **906.1 Fire Extinguishers**
 - Fire extinguishers shall be placed in approved locations as drawn by the code enforcement official on the approved plans.
 - The fire extinguishers provided shall have a minimum rating of 2A:10BC and shall not be installed higher than 5 feet above the finished floor

- **506.1 Knox Box**
 - A secure key box shall be installed on the new building that houses all keys to all the doors within the building in which the fire department would need access to in the event of an emergency
 - Box to be placed on the front of the building where the fire department would access and to be mounted no higher than 5'
 - Knox Box order form is included with this letter.
 - Each exterior door must have a small red Knox sticker. Stickers are on the order form.

- **505.1 Physical Address**
 - The physical address of the building shall be posted in a conspicuous place so that it can be seen on approach from the road, access road, and/or parking lot.
 - The numbers used to make up the physical address shall be at least 5 inches in height.

- **503.1.1 Fire Department Access**
 - The fire department access shall extend to within 150 feet of all portions of the facility.
 - The fire department access road shall be of an unobstructed width of not less than 20 feet and shall have an unobstructed vertical clearance of not less than 13 feet 6 inches.

- **703.1 Rated Fire Walls**
 - Fire walls should be installed according to their listing and all penetrations should be properly sealed with the same rating as the wall itself.
 - Clarify whether the storage portion of the building is a S-1 or S-2 type occupancy. In reference to the separated mixed use occupancy, an S-1 requires a 3 hour separation and S-2 requires a 2 hour separation.

Thank you again for submitting the plans for the office building. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office.

Again, thank you and we look forward to working with you during the construction period!

Sincerely,



Michael L. Martin
Deputy Fire Marshal
