

01-5-2948

HARNETT COUNTY HEALTH DEPARTMENT

No 18600

IMPROVEMENT PERMIT

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No Person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) PROGRESSIVE BUILDERS OF NC New Installation Septic Tank
Property Location: SR# US401 Repairs Nitrification Line

Subdivision SPENCE MILL INDUSTRIAL PARK Lot # 14

Tax ID # _____ Quadrant # _____

Number of Bedrooms Proposed: WAREHOUSE (15 EMPLOYEES) Lot Size: _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 100 ft.

Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.

Type of system: Conventional Other PUMP TO CONVENTIONAL

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface Drainage Field No. of ditches 2 exact length of each ditch 105 ft. width of ditches 3 ft. depth of ditches 18-30 in.

French Drain Required: 14 Linear feet

Date: 10/1/01

This permit is subject to revocation if site plans or intended use change.

Signed: _____
Environmental Health Specialist

- * SEE ATTACHED DRAWING FOR SYSTEM LAYOUT
- * MAINTAIN ALL SETBACKS
- * CONTRACTOR TO MEET ON SITE PRIOR TO INSTALLATION

HARNETT COUNTY HEALTH DEPARTMENT
AUTHORIZATION TO CONSTRUCT

Authorization is hereby given to construct a wastewater system to the specifications described by Harnett County Health Department Improvement Permit # 18600. This authorization shall be valid for a period not to exceed five (5) years from the date of issuance. This authorization will be invalid if ownership, site plans, or intended use change.

Owner or Authorized Agent PROGRESSIVE BUILDERS OF NC

Name: _____ Telephone # 919-568-3756

Address: PO 118 KIPLING NC 27543

Property Location: SR # US401 Road Name ~~SPENCE~~ BUTTONWOOD CT

New Installation Repair _____ Septic Tank Nitrification Lines

Subdivision SPENCE MILL IND. PARK Lot # 14

Number of Bedrooms Proposed: 15 EMPLOYEES Lot size: _____

Basement _____ With Plumbing _____ Without Plumbing _____

Water Supply: Well _____ Public Minimum Well Setback: 100 ft.

Type of System: Conventional Other _____

Tank Volume: Septic Tank 1000 gallons Pump Chamber 1000 gallons

Nitrification Field Specifications

Number of fields 1 Number of Lines per Field 2 Length of lines 105'

Width of ditches 3 ft. Depth of ditches 18-30 inches

French Drain: Linear feet required _____ Depth of gravel _____

No wastewater system shall be covered or placed into use by any person until an inspection by the Harnett County Health Department has determined that the system has been installed according to the conditions of the improvement permit and that a valid operations permit has been issued.

Authorized Agent for Harnett County Health Department

Name: [Signature] Date: 10/1/01