

HTE# 07-5-18150

Harriet County Department of Public Health

24221

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: EARL G CLACK
PROPERTY LOCATION: 561403 Cokesbury RD
SUBDIVISION: WOODMIND LOT # 59460
NEW [] REPAIR [x] EXPANSION []
Type of Structure: EX DWMH
Proposed Wastewater System Type: 25% REDUCTION SYSTEM
Projected Daily Flow: 360 GPD
Number of bedrooms: 3 Number of Occupants: 6 max
Basement [] Yes [x] No
Pump Required: [] Yes [] No [x] May be required based on final location and elevations of facilities
Type of Water Supply: [] Community [x] Public [x] Well Distance from well 50' feet
Permit valid for: [x] Five years [] No expiration

Authorized State Agent: James E. Manhan for Date: 8-16-07 SEE ATTACHED SITE SKETCH
The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: EARL G CLACK
PROPERTY LOCATION: 561403 Cokesbury RD
SUBDIVISION: WOODMIND LOT # 59460
Facility Type: EX DWMH [] New [] Expansion [x] Repair
Basement? [] Yes [x] No Basement Fixtures? [] Yes [x] No
Type of Wastewater System** 25% REDUCTION SYSTEM (Initial) Wastewater Flow: 360 GPD
(See note below, if applicable [])
25% REDUCTION SYSTEM (Repair)

Installation Requirements/Conditions

Septic Tank Size NEW 1000 gallons Exact length of each trench 2 X 100 feet Trench Spacing: 9 Feet on Center
Pump Tank Size _____ gallons Trenches shall be installed on contour at a Soil Cover: 6 inches
Maximum Trench Depth of: 30-18 inches (Maximum soil cover shall not exceed 36" above the trench bottom)
in all directions)
Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe
2 inches above pipe
12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: James E. Manhan for Date: 8-16-07 SEE ATTACHED SITE SKETCH
Construction Authorization Expiration Date: 8-16-12

HTE# 07-5-18150

Permit # 24221

Harnett County Department of Public Health Site Sketch

ISSUED TO: FARL G CIACK PROPERTY LOCATOR: 521403 Cokesbury RD
SUBDIVISION WOODHART LOT # 5160

Authorized State Agent: James E. Markland Date: 8-16-07

