

HTE# 07-5-1849

Harrison County Department of Public Health

24241

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 511802 LANE RD

ISSUED TO: CASPER BRENT JOHNSON

SUBDIVISION _____ LOT # _____

NEW REPAIR EXPANSION

Site Improvements required prior to Construction Authorization Issuance: _____

Type of Structure: SFD

Proposed Wastewater System Type: 25% REDUCTION SYSTEM

Projected Daily Flow: 240 GPD

Number of bedrooms: 2 Number of Occupants: 4 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well _____ feet

Permit valid for: Five years No expiration

Permit conditions: *STUB PLUMBING OUT ABOVE GRADE OF SIAB

IF NOT PLUMBING WELLS TO DEPT TO ACHIEVE 24" MAX DETACH DEPTH PUMP WELL THEN BE REQUIRED!

Authorized State Agent: James E. Manhart

Date: 9-26-07

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: CASPER BRENT JOHNSON

PROPERTY LOCATION: 511802 LANE RD

SUBDIVISION _____ LOT # _____

Facility Type: SFD New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% REDUCTION (Initial) Wastewater Flow: 240 GPD

(See note below, if applicable) 25% REDUCTION SYSTEM (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 2x 120 feet Trench Spacing: 9 Feet on Center

Pump Tank Size _____ gallons Trenches shall be installed on contour at a Soil Cover: 6 inches (Maximum soil cover shall not exceed 36" above the trench bottom)

Maximum Trench Depth of: 24" max inches (Trench bottoms shall be level to +/-1/4" in all directions)

Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: 6 inches below pipe

Conditions: *STUB PLUMBING OUT ABOVE GRADE OF SIAB! 2 inches above pipe 12 inches total

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: James E. Manhart

Date: 9-26-07

SEE ATTACHED SITE SKETCH

Construction Authorization Expiration Date: 9-26-12

HTE# 07-5-18419

Permit # 24241

Harnett County Department of Public Health Site Sketch

ISSUED TO: CASPER Brent Johnson PROPERTY LOCATOR: SR 1802 LANE RD
SUBDIVISION _____ LOT # _____

Authorized State Agent: James E. Manhart Date: 9-26-07

