

HTE# 07-5-17868

Harnett County Department of Public Health

23993

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: DONNIE LEE PROPERTY LOCATION: SIC 1803 LEE RD  
 SUBDIVISION \_\_\_\_\_ LOT # \_\_\_\_\_  
 NEW ☒ REPAIR ☐ EXPANSION ☐ Site Improvements required prior to Construction Authorization Issuance: \_\_\_\_\_  
 Type of Structure: MH  
 Proposed Wastewater System Type: 25% REDUCTION system  
 Projected Daily Flow: 360 GPD  
 Number of bedrooms: 3 Number of Occupants: 6 max  
 Basement ☐ Yes ☒ No  
 Pump Required: ☐ Yes ☐ No ☐ May be required based on final location and elevations of facilities  
 Type of Water Supply: ☐ Community ☐ Public ☒ Well Distance from well 50' feet Permit valid for: ☒ Five years  
 Permit conditions: \_\_\_\_\_ ☐ No expiration

Authorized State Agent: James E. Manhart Date: 7-3-07 SEE ATTACHED SITE SKETCH  
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: DONNIE LEE PROPERTY LOCATION: SIC 1803 LEE RD  
 SUBDIVISION \_\_\_\_\_ LOT # \_\_\_\_\_  
 Facility Type: MH ☒ New ☐ Expansion ☐ Repair  
 Basement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No  
 Type of Wastewater System\*\* 25% REDUCTION (Initial) Wastewater Flow: 360 GPD  
 (See note below, if applicable ☐)  
25% REDUCTION system (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons Exact length of each trench 4 x 60 feet Trench Spacing: 9 Feet on Center  
 Pump Tank Size \_\_\_\_\_ gallons Trenches shall be installed on contour at a Soil Cover: 6 inches  
 Maximum Trench Depth of: 22" MAX inches (Maximum soil cover shall not exceed 36" above the trench bottom)  
 (Trench bottoms shall be level to  $\pm 1/4"$  in all directions)  
 Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_\_ GPM Aggregate Depth: 6 inches below pipe  
 Conditions: \_\_\_\_\_ 2 inches above pipe  
12 inches total

\*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: \_\_\_\_\_ Date: \_\_\_\_\_

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

Authorized State Agent: James E. Manhart Date: 7-3-07  
 Construction Authorization Expiration Date: 7-3-08

SEE ATTACHED SITE SKETCH

HTE# 07-5-17868

Permit # 23993

# Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: SJ1803 LEE RD


ISSUED TO: DONNER LEE

SUBDIVISION

LOT #

Authorized State Agent: James C. Markham

Date: 7-3-07



SJ1803 LEE