

HTE# 10-5-252012

Harnett County Department of Public Health

26408

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 5101 Pecan Lane

SUBDIVISION: Henry Pope

LOT # 3

ISSUED TO: Charles Stevens

NEW ☒ REPAIR ☐ EXPANSION ☐

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: SFD

Proposed Wastewater System Type:

Projected Daily Flow: 480 GPD

Number of bedrooms: 4 Number of Occupants: 8 max

Basement ☐ Yes ☒ NoPump Required: ☐ Yes ☐ No ☒ May be required based on final location and elevations of facilitiesType of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well _____ feet

Permit valid for:

☒ Five years☐ No expiration

Permit conditions: Pump may be needed/required

STEPDOWNS WILL BE NEEDED

Authorized State Agent: [Signature] Date: 1-25-11

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Charles Stevens

PROPERTY LOCATION: 101 Pecan Ln

SUBDIVISION: Henry Pope

LOT # 3

Facility Type: SFD ☒ New ☐ Expansion ☐ RepairBasement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No

Type of Wastewater System** 25% REDUCTION

(Initial) Wastewater Flow: 480 GPD

(See note below, if applicable ☐)

25% REDUCTION (minor) (Repair)

Installation Requirements/Conditions

Septic Tank Size 1206 gallons

Pump Tank Size _____ gallons

Number of trenches 2

Exact length of each trench 180 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 20-718 inches

(Trench bottoms shall be level to $\pm 1/4"$

in all directions)

Trench Spacing: 9 Feet on Center

Soil Cover: 6 inches

(Maximum soil cover shall not exceed

36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

12 inches total

Conditions: Pump may be required

STEPDOWNS WILL BE NEEDED.

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____

Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature]

Date: 1-25-11

Construction Authorization Expiration Date: 1-25-16

HTE# 10-5-25201R

Permit # 26408

Harnett County Department of Public Health Site Sketch

ISSUED TO: Charles Stevens PROPERTY LOCATION: 101 Pecan Ln
SUBDIVISION Herring Pope LOT # 3

Authorized State Agent: James E. Markham for RILEY Date: 1-25-11

