

HTE# 15-5-3682712

Harnett County Department of Public Health

28589

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: 51543 ENNES RD

ISSUED TO: Kenneth Gander

SUBDIVISION

LOT # 4

NEW ☒ REPAIR ☐ EXPANSION ☐

Site Improvements required prior to Construction Authorization Issuance:

Type of Structure: moved sfb + add

Proposed Wastewater System Type: 25% reduction

Projected Daily Flow: 360 GPD

Number of bedrooms: 3 Number of Occupants: 6 max

Basement ☐ Yes ☒ NoPump Required: ☐ Yes ☐ No ☒ May be required based on final location and elevations of facilitiesType of Water Supply: ☐ Community ☒ Public ☐ Well Distance from well _____ feet

Permit valid for:

☒ Five years☐ No expiration

Permit conditions:

Authorized State Agent:

Date: 11-13-15

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Kenneth Gander

PROPERTY LOCATION: 51543 ENNES RD

SUBDIVISION

LOT # 9

Facility Type: moved sfb + add ☒ New ☐ Expansion ☐ RepairBasement? ☐ Yes ☒ No Basement Fixtures? ☐ Yes ☒ No

Type of Wastewater System** 25% reduction system (Initial) Wastewater Flow: 360 GPD

(See note below, if applicable ☐)

25% reduction system (Repair)

Installation Requirements/Conditions

Septic Tank Size 1000 gallons

Pump Tank Size _____ gallons

Number of trenches 3

Exact length of each trench 80 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 26" inches

(Trench bottoms shall be level to +/- 1/4"

in all directions)

Trench Spacing: 5 Feet on Center

Soil Cover: 6 inches

(Maximum soil cover shall not exceed

36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

12 inches total

Conditions:

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____

Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent:

Date: 11-13-15

Construction Authorization Expiration Date: 11-13-20

HTE# 15-5-36827R

Permit # 28589

Harnett County Department of Public Health Site Sketch

ISSUED TO: Kenneth Gardner PROPERTY LOCATOR: 512-1543 ENNES RD
SUBDIVISION _____ LOT # 4

Authorized State Agent: Jane E. Mankin Date: 11-13-15

