

Preliminary Soils Evaluation



Jorge Hernandez

~17.2 acres - Harnett County, NC

Site Plan approved
- Snow Boudh
12/20/17



Legend

-  Areas contain soils with 30 inches or more of useable material and have potential for conventional, modified conventional, LPP or ultra-shallow conventional septic systems. There may be inclusion of soils 24-29 inches to a restrictive horizon that will have potential for LPP septic systems.
-  Areas contain soils with 24 inches or more of useable material and have potential for Ultra-shallow conventional, LPP type septic systems.
- NE** Unsuitable or Not Evaluated

***Preliminary Soils Evaluation**
 *Soil boundary was sketched onto a preliminary map of the property supplied by the client's surveyor.
 *Not a Survey.
 *Septic system setbacks listed below for new lots.
 1) 10' from property lines.
 2) 100' from wells for primary systems.
 3) 50' from surface waters (streams, ponds, lakes).
 *Any mechanical disturbances such as grading, cutting and filling of the suitable soil areas can render areas unsuitable for future septic systems.
 *See accompanying report for additional information.
 *Due to Soil Variability, Adams soil consulting cannot guarantee that the areas shown as suitable will be permitted by the local Health Department.

*Not a Survey
(sketched from a Preliminary Plat)



GRAPHIC SCALE
1" = 200'



Adams
Soil Consulting
919-414-6761
Project #492