

HTE# 16-5-38103

Harnett County Department of Public Health

28819

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

PROPERTY LOCATION: SR1505 Pennridge RD

ISSUED TO: Dupree Farms LLC

SUBDIVISION _____ LOT # _____

NEW REPAIR EXPANSION

Site Improvements required prior to Construction Authorization Issuance: _____

Type of Structure: Farm Bldg

Proposed Wastewater System Type: 2500 REDUCER

Projected Daily Flow: 600 GPD

Number of bedrooms: _____ Number of Occupants: 25 Employees max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well _____ feet

Permit valid for: Five years No expiration

Permit conditions: _____

Authorized State Agent: James E. Manhart Date: 4-11-16

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Dupree Farms LLC

PROPERTY LOCATION: SR1505 Pennridge RD

SUBDIVISION _____ LOT # _____

Facility Type: _____ New Expansion Repair

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** Pump to 2500 REDUCER system (Initial) Wastewater Flow: 600 GPD

(See note below, if applicable). Pump to 2500 REDUCER (Repair)

Installation Requirements/Conditions

Septic Tank Size 1500 gallons

Pump Tank Size 1500 gallons

Number of trenches 3

Exact length of each trench 120 feet

Trenches shall be installed on contour at a

Maximum Trench Depth of: 24 inches

(Trench bottoms shall be level to +1-1/4"

in all directions)

Trench Spacing: 9 Feet on Center

Soil Cover: 6 inches

(Maximum soil cover shall not exceed

36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: 6 inches below pipe

2 inches above pipe

12 inches total

Conditions: _____

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.

NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: James E. Manhart Date: 4-11-16

Construction Authorization Expiration Date: 4-11-21

HTE# 16-5-58183

Permit # 28819

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: SL 1505 Pearlidge RD

ISSUED TO: DUPREE FARMS LLC

SUBDIVISION _____

LOT # _____

Authorized State Agent: _____

James S. Manhart ~~FEET~~ REGAS

Date: 4-11-16

