

HTE 04-5-8519

# OPERATIONS PERMIT

Name: (owner) Weaver Dev. Corp.  New Installation  Septic Tank  
 Property Location: SR# 1141  Repairs  Nitrification Line  
 Subdivision Sunset Ridge Lot # 174  
 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: Larry Shaep Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:   
 Water Supply:  Well  Public  Community  
 Distance From Well: 50 ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other \_\_\_\_\_

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 200 ft. width of ditches 3 ft. depth of ditches 18-30 in.

French Drain Required: \_\_\_\_\_ Linear feet

Date: ~~11-01-03~~ 11-01-04

Inspected by: [Signature]  
 Environmental Health Specialist

PERMIT NO. 21093

