

HTE 04-5-9995

HAMILTON COUNTY HEALTH DEPARTMENT  
ENVIRONMENTAL HEALTH SECTION

16569

# OPERATIONS PERMIT

Name: (owner) MOORE & MOORE  New Installation  Septic Tank  
 Property Location: SR# 1116 Doss Rd  Repairs  Nitrification Line  
 Subdivision COLONIAL HILLS Lot # 17  
 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: HAROLD CARTER & BROS Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 100 ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other \_\_\_\_\_

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field	No. of ditches <u>3</u>	exact length of each ditch <u>60</u> ft.	width of ditches <u>3</u> ft.	depth of ditches <u>24-36</u> in.
------------------------------	----------------------------	---	----------------------------------	--------------------------------------

French Drain Required: \_\_\_\_\_ Linear feet

Date: 11/12/04

Inspected by: [Signature] RS  
Environmental Health Specialist

PERMIT NO. 20945

