

HTE 04-50010035

# OPERATIONS PERMIT

Name: (owner) WELLONS REALTY INC  New Installation  Septic Tank  
 Property Location: SR# 217 SLASH CIRCLE  Repairs  Nitrification Line  
 Subdivision THE PINES Lot # 3  
 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Contractor: JAMES BAREFOOT Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50 ft.

**Following are the specifications for the sewage disposal system on above captioned property.**

Type of system:  Conventional  Other PUMP TO CONVENTIONAL

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface	No. of	exact length	width of	depth of
Drainage Field	ditches <u>2</u>	of each ditch <u>60</u> ft.	ditches <u>3</u> ft.	ditches <u>24</u> in.

French Drain Required: \_\_\_\_\_ Linear feet

Date: 1/25/05  
 Inspected by: [Signature] RS  
 Environmental Health Specialist

PERMIT NO. 21248

DRAWING  
NOTES

\* TANKS & LINES  
INSPECTED ON  
11/29/04 BY  
OT

\* PUMP & ALARM  
STILL TO BE  
CHECKED

