

HTE # 04-5-10777

HAI TT COUNTY HEALTH DEPART NT
ENVIRONMENTAL HEALTH SECTION

17475

OPERATIONS PERMIT

Name: (owner) Hammerton Builders New Installation Septic Tank Repair

Property Location: SR# 1435 Tripp RD Nitrification Line Expansion

Subdivision Plantation Viewland Lot # 58 Tax ID # _____ Quadrant # _____

Contractor: Reck Holland Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50' ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other 25% Reduction System

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 80 ft. width of ditches 3 ft. depth of ditches 24 in.

French Drain Required: - Linear feet Date: 3-29-05

PERMIT NO. 21429 Inspected by: James E. Mantel

