

HTE # 05-50011178

HA TT COUNTY HEALTH DEPART NT
ENVIRONMENTAL HEALTH SECTION

17593

OPERATIONS PERMIT

Name: (owner) Sole Home (Kenneth Jordan) New Installation Septic Tank Repair

Property Location: SR# 1115 Nitrification Line Expansion

Subdivision Crestview Est Lot # 185 Tax ID # _____ Quadrant # _____

Contractor: ~~Crestview~~ ~~Est~~ Ted Brown Registration # 1

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other 25% Reduction SYSTEM Chamber

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons Chamber

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 150 ft. width of ditches 3 ft. depth of ditches 18 1/2 in.

French Drain Required: _____ Linear feet Date: 5-2-05

PERMIT NO. 21531 Inspected by: J. W. ...

