

HTE # 11461

HANCOCK COUNTY HEALTH DEPARTMENT  
ENVIRONMENTAL HEALTH SECTION

17923

# OPERATIONS PERMIT

Name: (owner) Bradley Built Homes Inc  New Installation  Septic Tank  Repair

Property Location: SR# 1415 Rawls CR-120  Nitrification Line  Expansion

Subdivision ALEX PLACE Lot # 18 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_

Contractor: MIKE RAY Registration # 64

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other Monitor 25% Reduction

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface Drainage Field No. of ditches 2 exact length of each ditch 120 ft. width of ditches 3 ft. depth of ditches 18-20 in.

French Drain Required: - Linear feet

Date: 9-8-05

PERMIT NO. 21878

Inspected by: James E. Mantel

