

HTE 05-5-11462

# IMPROVEMENT PERMIT

21646

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No Person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) STANCIU BUILDERS INC  New Installation  Septic Tank  
 Property Location: SR# 1415 IRONS CHURCH RD  Repairs  Nitrification Line

Subdivision Alex PINE Lot # 5

Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_

Number of Bedrooms Proposed: 3 Lot Size: .81

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50' ft.

**Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.**

Type of system:  Conventional  Other 25% Reduction System

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 75 ft. width of ditches 3 ft. depth of ditches 22" → 18" in.

French Drain Required: - Linear feet

Date: 3-14-05

**This permit is subject to revocation if site plans or intended use change.**

Signed: James E. Markham  
 Environmental Health Specialist

