

HTE 05-5001787

# IMPROVEMENT PERMIT

21695

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No Person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) SHOWCASE CONSTRUCTION  New Installation  Septic Tank  
Property Location: SR# 1124 RAMBLER RD  Repairs  Nitrification Line

Subdivision WESTERFIELD FARMS Lot # 17

Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_

Number of Bedrooms Proposed: 3 Lot Size: .45ac

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 100 ft.

**Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.**

Type of system:  Conventional  Other PUMP TO CONVENTIONAL

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 18-24 in.

French Drain Required: \_\_\_\_\_ Linear feet

Date: 5/5/05

Signed: [Signature] ES (OLIVER TOLKOFF)  
Environmental Health Specialist

**This permit is subject to revocation if site plans or intended use change.**

- \* START LINES @ 18" DEEP. RUN FOR ABOUT 60' AND THEN STEP DOWN TO 24"
- \* MAINTAIN ALL SETBACKS
- \* CALL WITH ANY QUESTIONS PRIOR TO INSTALLATION



