

HTE # 05-500-11881

HARNE COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH SECTION

17898

OPERATIONS PERMIT

Name: (owner) Steve Terison (Self Home) New Installation Septic Tank Repair

Property Location: SR# 1115 Nitrification Line Expansion

Subdivision Crestview Lot # 232 Tax ID # _____ Quadrant # _____

Contractor: Ted Brown Registration # _____

Basement with Plumbing: Garage: Lines on Tanks on 9-22-05
Water Supply: Well Public Community gha

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other buried 25' to bedrock STS 76a

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 225 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain Required: _____ Linear feet Date: 10-21-05

PERMIT NO. 22663 Inspected by: Jan [Signature]

