

HTE # 055001181R

OPERATIONS PERMIT

Name: (owner) HAMILTON BUILDERS New Installation Septic Tank Repair

Property Location: SR# 1300 OAK ST Nitrification Line Expansion

Subdivision PINE HILLS Lot # 1 Tax ID # _____ Quadrant # _____

Contractor: LARRY SHARPE Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 100 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other TIRE CHIPS

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 4 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 18 in.

French Drain Required: _____ Linear feet

Date: 11/9/05

PERMIT NO. 22094

Inspected by: [Signature] RS

