

HTE # 05-52012247

OPERATIONS PERMIT

Name: (owner) Caviness New Installation Septic Tank Repair

Property Location: SR# 1125 Nitrification Line Expansion

Subdivision Forest Oaks Lot # 14 Tax ID # _____ Quadrant # _____

Contractor: D.C. Carter Registration # _____

Basement with Plumbing: Garage:

*Needs filter & fine chips removed
3-3-06*

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other Tine Chips

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 1 exact length of each ditch 200 ft. width of ditches 3 ft. depth of ditches 18-24 in.

French Drain Required: _____ Linear feet Date: 4-10-06

PERMIT NO. 21763 Inspected by: J. W. [Signature]

