

HTE # 05-5-13045

OPERATIONS PERMIT

Name: (owner) (Riverstone) Duncan Development New Installation Septic Tank Repair

Property Location: SR# 1403 Nitrification Line Expansion
Subdivision Cokerbury Park Lot # 26 Tax ID # _____ Quadrant # _____

Contractor: Kirby Johnson Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other E2 Flow

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 80 ft. width of ditches 3 ft. depth of ditches 18-24 in.

French Drain Required: _____ Linear feet Date: 12/14/2005

PERMIT NO. 22261 Inspected by: Bryan McSwain, P.E.

