

HTE#05-50013666R

IMPROVEMENT PERMIT 22841

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) HENRY SPEARS New Installation Septic Tank Repair
 Property Location: SR# 1769 OLD STAGE Nitrification Line Expansion
 Subdivision HENRY LEWIS SPEARS Lot # B1
 Tax ID# _____ Quadrant # _____
 Number of Bedrooms Proposed: 3 (360 gpd) Lot Size: 1 AC

Basement with Plumbing: Garage:
 Water Supply: Well Public Community
 Distance From Well: 100 ft.

Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.

Type of system: Conventional Other 25% REDUCTION SYSTEM ^{PUMP TO}

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface No. of exact length width of depth of
 Drainage Field ditches 2 of each ditch 113 ft. ditches 3 ft. ditches 18 in.


French Drain Required: 138 Linear feet

Date: 4/5/06
PERMIT EXPIRES 5 YEARS FROM ABOVE DATE

This permit is subject to revocation if site plans or intended use change.

Signed: [Signature] AS (OLIVER TOLKSON)
 Environmental Health Specialist

- * FRENCH DRAIN
138' LONG
1' WIDE
MINIMUM 36" DEEP
- * PUMP
23 gpm @ 14.3'
- * MAINTAIN ALL
SETBACKS
- * CALL WITH ANY
QUESTIONS PRIOR
TO INSTALLATION



HARNETT COUNTY DEPARTMENT OF PUBLIC HEALTH AUTHORIZATION TO CONSTRUCT

Authorization is hereby given to construct a wastewater system to the specifications described by Harnett County Department of Public Health, Improvement Permit # 22841. This authorization shall be valid for a period not to exceed five (5) years from the date of issuance. ***This authorization will be invalid if ownership, site plans, or intended use change.***

HENRY L SPEARS 980-1834
Name Telephone #

PO Box 166 Edwin NC 28339
Address

1769 Old Stage Rd
Property Location SR# Road Name

HENRY LEWIS SPEARS B1 3 (360gpd) 1 ac
Subdivision Lot # # Bedrooms Proposed Lot Size

TYPE OF SYSTEM

- New Installation Repair Septic Tank Nitrification Lines
 Conventional Other Pump To 25% REDUCTION SYSTEM
 Basement With Plumbing Without Plumbing

Water Supply: Well Public Water Supply Minimum Well Setback: 100 Ft.

Septic Tank 1000 gal Pump Chamber 1000 gal

NITRIFICATION FIELD SPECIFICATIONS

Number of fields 1 # of lines per field 2 Length of lines 113 Ft.

Width of ditches 3 ft. Depth of ditches 18 inches

French Drain: Linear feet required 138 Depth of gravel 36"

No wastewater system shall be covered or placed into use by any person until an inspection by the Harnett County Health Department has determined that the system has been installed according to the conditions of the Improvement Permit and that a valid Operations Permit has been issued.


Signature of Authorized Agent for Harnett County

4/5/06
Date