

HTE# 0550013680

# IMPROVEMENT PERMIT 22472

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) OAK CITY HOMES New Installation  Septic Tank  Repair   
 Property Location: SR# 1437 BALLARO RD Nitrification Line  Expansion   
 Subdivision BALLARO WOODS Lot # 68  
 Tax ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
 Number of Bedrooms Proposed: 3 (360 gpd) Lot Size: .58

Basement with Plumbing:  Garage:   
 Water Supply:  Well  Public  Community  
 Distance From Well: 50 ft.

**Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.**

Type of system:  Conventional  Other PUMP TO 25% REDUCTION SYSTEM

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface No. of exact length width of depth of  
 Drainage Field ditches 3 ft. of each ditch 100 ft. ditches 3 ft. ditches 24-18 in.

French Drain Required: \_\_\_\_\_ Linear feet

Date: 1/11/06  
 PERMIT EXPIRES 5 YEARS FROM ABOVE DATE

**This permit is subject to revocation if site plans or intended use change.**

Signed: [Signature] RS (OLIVER TOLKSCOFF)  
 Environmental Health Specialist

\* CALL AFTER LOT IS CLEARED FOR FINAL LAYOUT

\* CONSTRUCTION AUTHORIZATION TO BE ISSUED AFTER FINAL LAYOUT

