

HTE # 05-5003725

HAMMONT COUNTY HEALTH DEPARTMENT  
ENVIRONMENTAL HEALTH SECTION

18220

# OPERATIONS PERMIT

Name: (owner) HAMPTON CUSTOM BUILDERS INC  New Installation  Septic Tank  Repair

Property Location: SR# 1437 BALLARD RD  Nitrification Line  Expansion

Subdivision BALLARD WOODS Lot # 40 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_

Contractor: TOMMY COLEY Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other POLYSTYRENE AGGREGATE TRENCH

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of ditches 4 exact length of each ditch 75 ft. width of ditches 3 ft. depth of ditches 24-36 in.

French Drain Required: \_\_\_\_\_ Linear feet Date: 4/5/06

PERMIT NO. 22471 Inspected by: [Signature] ES

