

HTE # 06-5-138612

HAMILTON COUNTY HEALTH DEPARTMENT
ENVIRONMENTAL HEALTH SECTION

18158

OPERATIONS PERMIT

Name: (owner) Strong Built Homes New Installation Septic Tank Repair

Property Location: SR# 1465 Nitrification Line Expansion

Subdivision Dynchar Place Lot # 32 Tax ID # _____ Quadrant # _____

Contractor: Jason Matthews Registration # _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system: Conventional Other E2 Flow

Size of tank: Septic Tank: 1000 gallons Pump Tank: _____ gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 20 in.

French Drain Required: _____ Linear feet Date: 5/9/2006

PERMIT NO. 22803 Inspected by: Bryan McFinn, R.S.

