

03-5-6150

IMPROVEMENT PERMIT

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No Person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) William Pullen

New Installation Septic Tank

Property Location: SR# 1403 Cokerbury Rd.

Repairs Nitrification Line

Subdivision Cokerbury Park Lot # 9

Tax ID # _____ Quadrant # _____

Number of Bedrooms Proposed: 3 Lot Size: _____

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50 min. ft.

Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.

Type of system: Conventional Other Pump to Alternating dual fields utilizing 25% reduction system

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface Drainage Field: No. of ditches 6 exact length of each ditch 75 ft. width of ditches 3 ft. depth of ditches 12 in. MAX 6 in. of cover


French Drain Required: _____ Linear feet

Date: 2/6/2003

This permit is subject to revocation if site plans or intended use change.

Signed: Bryan McSwain R.S.
Environmental Health Specialist

- * Maintain all setbacks
- * 50' off pond
- * 2 fields with 3 lines each
- * Each field with its own D-Box
- * Fields to be separated by Bull Run valve
- * Lines to be run on contour + NO DEEPER than 12 inches
- * 6 inches of cover required over system
- * Fields to be alternated every 6 months



HARNETT COUNTY HEALTH DEPARTMENT
AUTHORIZATION TO CONSTRUCT

Authorization is hereby given to construct a wastewater system to the specifications described by Harnett County Health Department, Improvement Permit # 19743. This authorization shall be valid for a period not to exceed five (5) years from the date of issuance. This authorization will be invalid if ownership, site plans, or intended use change.

Name William Pullen Telephone# 919-557-8004

Address P.O. Box 128 Foysey Virginia N.C. 27526

Property Location SR# 1403 Road Name Cokesbury

Subdivision Cokesbury Park Lot # 9 # Bedrooms Proposed 3 Lot Size _____

TYPE OF SYSTEM

- New Installation Repair Septic Tank Nitrification Lines
 Conventional Other Pump to dual Alternating fields utilizing 25% reduction system
 Basement With Plumbing Without Plumbing

Water Supply: Well Public Water Supply Minimum Well Setback: 50 Ft.

Septic Tank 1000 gal Pump Chamber 1000 gal

NITRIFICATION FIELD SPECIFICATIONS

Number of fields 2 # of lines per field 3 Length of lines 75 Ft.

Width of ditches 3 ft. Depth of ditches 12 inches MAX
6 inches feeder

French Drain: Linear feet required _____ Depth of gravel _____

No wastewater system shall be covered or placed into use by any person until an inspection by the Harnett County Health Department has determined that the system has been installed according to the conditions of the Improvement Permit and that a valid Operations Permit has been issued.

Bryan R. L. S.
Signature of Authorized Agent for Harnett County of Harnett

2/6/2007
Date