

HTE # 06-5-14517

# OPERATIONS PERMIT

Name: (owner) CMA Builders LLC  New Installation  Septic Tank  Repair

Property Location: SR# 1403 HARVEY Canal  Nitrification Line  Expansion

Subdivision PAN MEADOW Lot # 21 Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_

Contractor: Reck Holland Registration # \_\_\_\_\_

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 50 ft.

Following are the specifications for the sewage disposal system on above captioned property.

Type of system:  Conventional  Other 75% REDUCTION system

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field	No. of ditches <u>4</u>	exact length of each ditch <u>75</u> ft.	width of ditches <u>3</u> ft.	depth of ditches <u>30-48</u> in.
------------------------------	----------------------------	---	----------------------------------	--------------------------------------

French Drain Required: - Linear feet

Date: 9-18-06

PERMIT NO. 22887

Inspected by: James E. Markant

