

HTE# 06-5-14605

# IMPROVEMENT PERMIT 22982

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) BRIAN JOHNSON BUILDERS New Installation  Septic Tank  Repair   
Property Location: SR# 1452 TRUVELOVE RD Nitrification Line  Expansion   
Subdivision TAYLOR POINTE Lot # 7  
Tax ID# \_\_\_\_\_ Quadrant # \_\_\_\_\_  
Number of Bedrooms Proposed: 3 (360 gpd) Lot Size: 21885 ft<sup>2</sup>

Basement with Plumbing:  Garage:   
Water Supply:  Well  Public  Community  
Distance From Well: 100 ft.

**Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.**

Type of system:  Conventional  Other PUMP TO 25% REDUCTION PLUS REPAIR

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface No. of exact length width of depth of  
Drainage Field ditches 2 of each ditch 170 ft. ditches 3 ft. ditches 18 in.

French Drain Required: \_\_\_\_\_ Linear feet

Date: 5/1/06  
PERMIT EXPIRES 5 YEARS FROM ABOVE DATE

**This permit is subject to revocation if site plans or intended use change.**

Signed: [Signature] RS (OLIVER TOLKBOFF)  
Environmental Health Specialist

- \* THIS SYSTEM REQUIRES THE INSTALLATION OF THE INITIAL & REPAIR AT ONE TIME.
- \* THERE WILL BE 2 170' LINES. INSTALL BULL RUN VALVE TO BE ABLE TO SWITCH BETWEEN SYSTEMS.
- \* CALL WITH ANY QUESTIONS PRIOR TO INSTALLATION

