

IMPROVEMENT PERMIT

No 14314

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No Person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) Michael Anderson

New Installation Septic Tank

Property Location: SR#1443 Lafayette Rd

Repairs Nitrification Line

Subdivision V.H Lot # 155

Tax ID # Quadrant #

Number of Bedrooms Proposed: 3 BR 360 GPD Lot Size: 28,772 sqft

Basement with Plumbing: Garage:

Water Supply: Well Public Community

Distance From Well: 50' ft.

Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.

Type of system: Conventional Other MANATEE to 25% Reduction System

Size of tank: Septic Tank: 1000 gallons Pump Tank: 1000 gallons

Subsurface Drainage Field No. of ditches 3 exact length of each ditch 120 ft. width of ditches 3 ft. depth of ditches 26-28 in.

French Drain Required: Linear feet


Date: 5-23-06

This permit is subject to revocation if site plans or intended use change.

Signed: James E. Montfort Environmental Health Specialist

- * PUMP 40 gpm @ 11' TDH
* MANATEE 3 3/4" SCH40 VALVES 2' PRESSURE HEAD 2" SCH40 PIPE

* STEPDOWNS WILL BE NEEDED!



HARNETT COUNTY DEPARTMENT OF PUBLIC HEALTH AUTHORIZATION TO CONSTRUCT

Authorization is hereby given to construct a wastewater system to the specifications described by Harnett County Department of Public Health, Improvement Permit # 14314. This authorization shall be valid for a period not to exceed five (5) years from the date of issuance. *This authorization will be invalid if ownership, site plans, or intended use change.*

Michael Anderson Name 919-868-8294 Telephone #

180 WOODLAND RIDGE DR F.V. N.C. 27526 Address

1443 Property Location SR# Lafayette Road Name

V.H. Subdivision 155 Lot # 3BEN 3606PD # Bedrooms Proposed 28,772 sq ft Lot Size

TYPE OF SYSTEM

New Installation Repair Septic Tank Nitrification Lines

Conventional Other Monitored to 25% Reduction Syst

Basement With Plumbing Without Plumbing

Water Supply: Well Public Water Supply Minimum Well Setback: _____ Ft.

Septic Tank 1000 gal Pump Chamber 1000 gal

NITRIFICATION FIELD SPECIFICATIONS

Number of fields 2 # of lines per field 3 Length of lines 120 Ft.

Width of ditches 3 ft. Depth of ditches 26-718" max inches

French Drain: Linear feet required - Depth of gravel -

No wastewater system shall be covered or placed into use by any person until an inspection by the Harnett County Health Department has determined that the system has been installed according to the conditions of the Improvement Permit and that a valid Operations Permit has been issued.

James E. Mathan
Signature of Authorized Agent for Harnett County

5-24-06
Date